

FT4 Twin Pac



Project Profile Sheet

Owner: Wellhead Power Panoche, LLC
Location: Panoche, California
Owners Engineer: IEC Corporation
Output: 50 MW
Time Line: August 2001 to October 2001
50 MW in 50 Days

Scope:

Installation of an FT4 Twin Pac Combustion Turbine Generator. The facility was dismantled in Brownsville, TX and relocated to Panoche, CA. This included foundations, undergrounds, electrical, piping, mechanical and start-up support. TTS Construction self performed a majority of the work.

The turbines were refurbished while the project was in progress. At the same time as dismantle, TTSC was working with the engineers on supporting the fast track design. The greenfield site was being constructed at the same time as the dismantle. The project was completed from start to finish in 50 days.

Project Keys:

- Refurbishment of equipment
- Fast Track Schedule
- Integration into an existing live facility

